

Project Name: DPSS Digital Display Project**Document A – Material List**

It is the contractor's responsibility to insure all labor and material needed to deliver a complete, fully functional system that complies with all applicable codes, RCIT and industry standards / best practices is accounted for in their cost proposal. The following is not intended to be a complete material list, but a clarification on certain items specified within the scope of services in Appendix A.

A/V Systems

Material/Labor Description	Part Number	Manufacturer
LANmark - 6 FTP Plenum Category 6 F/UTP (Yellow)	10062608	Berk-Tek
Ivory Atlas-X1 Cat 6 Shielded (AV)	61SJK-RI6	Leviton
24-Port - Flat Shielded QuickPort Patch Panel Empty, 1RU	4S255-S24	Leviton
5' Yellow Patch Cord - Cat 6 Shielded	CEX-HC6YWBT-SHL-5FT	Cable Exchange
9' Yellow Patch Cord - Cat 6 Shielded	CEX-HC6YWBT-SHL-9FT	Cable Exchange
Large Fusion Adjustable Wall Mount Bracket	LTM1U	Chief
Magicinfo Player v.7.1 Unified License 1 client	BW-MIP70PA	Samsung

Miscellaneous

Material/Labor Description	Part Number	Manufacturer
6' 12 Gauge Seismic Ceiling Wire With 3" Wood Eye Lag (100 Per Pack)		
CABLECAT J-Hook with Rod/Wire Clip (3/4", Small, 40 Per Box)	CAT124Z34	Erico
HILTI Toggle Bolt 1/4 inch	HTB Toggle Bolt	HILTI