

Project Name: DCSS Soundmasking Project**Document A – Material List**

It is the contractor's responsibility to insure all labor and material needed to deliver a complete, fully functional system that complies with all applicable codes, RCIT and industry standards / best practices is accounted for in their cost proposal. The following is not intended to be a complete material list, but a clarification on certain items specified within the scope of services in Appendix A.

Station Cabling

Material/Labor Description	Part Number	Manufacturer
LANmark-1000, UTP, 4 Pair, Cat 6 - Plenum (White)	10032092	Berk-Tek
White eXtreme Cat 6 - Single (900 Series)	61110-RW6	Leviton
7' White eXtreme Cat 6 UTP SlimLine Patch Cord	6D460-07W	Leviton
1 Pr 18 AWG - Plenum two conductor Cable	C3112.41.86	General

A/V Systems

Material/Labor Description	Part Number	Manufacturer
i.Net Headend Soundmasking Rack Unit	G8350	Lencore
i.Net Extended Service and Product Replacement Program	Extended Service	Lencore
Data Terminator	G21	Lencore
IP Data Bridge Transmitter Enclosure-Instreamer	G62470-IN	Lencore
i.Net Quad OP 1RU	G1525	Lencore
i.Net Speaker Brushed aluminum housing RJ45 universal	G545-U	Lencore
Commissioning Tuning and Balancing	Tune	Lencore
IP Data Bridge Transmitter Enclosure-Extreamer	G62471-EX	Lencore

Miscellaneous

Material/Labor Description	Part Number	Manufacturer
6' 12 Gauge Seismic Ceiling Wire With 3" Wood Eye Lag (100 Per Pack)		
CABLECAT J-Hook with Rod/Wire Clip (3/4", Small, 40 Per Box)	CAT124Z34	Erico